

# DUBAI VILLA PROJECT - BILL OF QUANTITIES

Section 16: Electrical & Mechanical Services - issued for procurement

| Item                               | Description                                 | Qty   | Unit | Make       |
|------------------------------------|---------------------------------------------|-------|------|------------|
| <b>ELECTRICAL WORKS VILLAS 1 6</b> |                                             |       |      |            |
| A.1                                | 4C x 16mm XLPE/SWA/PVC Cu cable, 0.6/1kV    | 1,200 | mtr  | Ducab      |
| A.2                                | 4 core x 35 sq.mm XLPE armoured cable       | 450   | mtr  | Ducab      |
| A.3                                | Single core PVC wire 2.5 sqmm               | 60    | coil | Ducab      |
| A.4                                | Single core PVC wire 4 sqmm                 | 25    | coil |            |
| A.5                                | 13A twin switched socket outlet, white      | 180   | nos  | MK         |
| A.6                                | Light switch 1 gang 2 way                   | 140   | nos  | MK         |
| A.7                                | MCB 1P 20A C curve 10kA                     | 90    | nos  | Schneider  |
| A.8                                | RCBO 32A 30mA                               | 24    | nos  | Schneider  |
| A.9                                | Distribution board TPN 18 way               | 6     | nos  | Schneider  |
| A.10                               | PVC conduit 20mm heavy gauge                | 2,400 | mtr  |            |
| A.11                               | LED downlight 12W 4000K                     | 260   | nos  | Philips    |
| <b>Sub total Electrical</b>        |                                             |       |      |            |
| <b>HVAC WORKS</b>                  |                                             |       |      |            |
| B.1                                | Copper refrigerant pipe 5/8 inch            | 600   | mtr  |            |
| B.2                                | Copper refrigerant pipe 3/8 inch            | 600   | mtr  |            |
| B.3                                | Armaflex pipe insulation 19mm thk           | 1,100 | mtr  | Armaflex   |
| B.4                                | Fan coil unit ducted 2 TR                   | 12    | nos  | Carrier    |
| B.5                                | Square ceiling diffuser 600x600             | 48    | nos  |            |
| <b>PLUMBING</b>                    |                                             |       |      |            |
| C.1                                | PPR pipe PN20 25mm                          | 900   | mtr  | Cosmoplast |
| C.2                                | PPR elbow 25mm                              | 300   | nos  | Cosmoplast |
| C.3                                | uPVC drainage pipe 110mm                    | 240   | mtr  |            |
| C.4                                | Ball valve 3/4 inch brass full bore         | 36    | nos  |            |
| C.5                                | Marble threshold installation - labour only | 1     | lot  |            |